



Proposal Number: COOLD18001
1/30/2018

MR. MATT RENCHER
PUBLIC WORKS DIRECTOR / CITY ENGINEER
355 S FIRST STREET
COOLIDGE, AZ 85128

MILL 2" DEPTH AND PAVE 2" MAG 3/4" MARSHALL ASPHALT
CITY OF COOLIDGE

Gentlemen:

DBA Construction, Inc. proposes to furnish all labor, equipment and materials (unless otherwise noted) to complete these items as listed. We thank you for the opportunity to submit a proposal for the project referenced.

ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	EXTENSION
1	1	LS	DBA MOBILIZATION	\$2,250.00	\$ 2,250.00
2	1	LS	MILL MACHINE MOBILIZATION	\$3,750.00	\$ 3,750.00
3	1	LS	PAVER MOBILIZATION	\$1,500.00	\$ 1,500.00
4	265	LF	SAWCUT ASPHALT	\$2.90	\$ 768.50
5	2709	SY	2" MILL AT CUL-DE-SAC	\$3.75	\$ 10,158.75
6	12772	SY	2" MILL AT MAINLINE	\$1.85	\$ 23,628.20
7	15481	SY	TACK	\$0.20	\$ 3,096.20
8	2709	SY	2" ASPHALT - CUL-DE-SAC	\$12.50	\$ 33,862.50
9	12772	SY	2" ASPHALT - MAINLINE	\$10.75	\$ 137,299.00
10	1	LS	SURVEY	\$4,640.00	\$ 4,640.00
11	1	LS	QUALITY CONTROL MATERIAL TESTING	\$2,835.00	\$ 2,835.00

PROPOSAL TOTAL:					\$ 223,788.15
------------------------	--	--	--	--	----------------------

OPTION PRICING					\$ -
ITEM #	QTY.	UNIT	DESCRIPTION	UNIT PRICE	EXTENSION
12	1	EA	DRYWELL	\$17,500.00	\$ 17,500.00

TAX BASED ON PROPOSAL TOTAL = \$13,865.13



Assumptions

Our proposal is based on assuming that the following conditions exist at the project site:

1. This proposal is based on milling 2" of the existing asphalt, placement of tack oil and paving 2" MAG ¾" Marshall. Quantities are based on exhibit given By Coolidge labeled 'Area C'.
2. Traffic control will be by others
3. Utility lowering and adjustments will be by others.
4. Water will be provided by City of Coolidge. The assumed location is the standpipe at Kenworthy and Coolidge Ave.

Clarifications

Our proposal requires further clarification on these points in order to be considered:

1. All permits will be by others.
2. Asphalt will be MAG ¾ Marshall.
3. Taxes will be billed at time of invoice.
4. Millings will be hauled to Kenworthy and Coolidge Ave or City of Coolidge pit
5. The option pricing for drywell includes abandoning the existing drywell, slurry backfill, trenching across to a new single chamber drywell.

Exclusions

Our proposal excludes the following items and was not considered during the preparation of this estimate:

1. Bonds
2. Grading
3. Import of base material

DBA CONSTRUCTION, INC.

MATT WOOLWINE

PROJECT MANAGER